
GROSS ROAD CULVERT REPLACEMENT

TOWNSHIP OF MUSKOKA LAKES T-2025-38





ISSUED FOR TENDER

JULY 9, 2025 PROJECT 225020



INDEX

DRAWING DESCRIPTION TP.01 TITLE PAGE IN.01 PP.01 PLAN AND PROFILE GA.01 GENERAL ARRANGEMENT EP.01 ENVIRONMENTAL PROTECTION

LEGEND

LEGEND		
ITEM PROPERTY LINE	EXISTING	PROPOSED
LOT LINE		
CENTRELINE		
EDGE OF ASPHALT		
CONCRETE CURB		
EDGE OF GRAVEL SHOULDER		
DITCH/DIRECTION OF FLOW		·
DRAINAGE SWALE/DIRECTION OF FLOW	4	
WATERMAIN/SIZE	150ø_W/M	150ø W/M
WATER SERVICE		
FIRE HYDRANT	- \(\rightarrow \	+ HYD
EXISTING WATER VALVE	₩ W	₩ wv
CURB STOP VALVE	⊠ csv	₩ CSV
WATERMAIN PLUG AND THRUST BLOCK		
WATERMAIN PLOG AND THROST BLOCK WATERMAIN BLOWOFF	□ BLOWOFF	⊘ ^{BLOWOFF}
		-
NATERMAIN REDUCER		200ø_SAN
SANITARY SEWER/SIZE/DIRECTION OF FLOW	7	
SANITARY MAINTENANCE HOLE	○ SAN MH	SAN MH
SANITARY SERVICE		
SANITARY FORCEMAIN	375ø STM	375ø STM
STORM SEWER/SIZE/DIRECTION OF FLOW	375ø_STM	
STORM MAINTENANCE HOLE	○ STM MH	● STM MH
CATCH BASIN	□ CB	■ CB4
DOUBLE CATCH BASIN	DCB	■ DCB4
CATCH BASIN MAINTENANCE HOLE	<i>□ СВМН</i>	• СВМН4
DOUBLE CATCH BASIN MAINTENANCE HOLE	□ DCBMH	□ DCBMH4
DITCH INLET CATCH BASIN	□ DICB	■ DICB4
CULVERT		
BELL UNDERGROUND	BU	BU
BELL AERIAL	———— BA ————	——— ВА ———
CABLE UNDERGROUND	CU	cu
CABLE AERIAL		
HYDRO UNDERGROUND		——— ни ———
HYDRO AERIAL	——— НА ———	——— на ———
GAS MAIN/SERVICE	GAS	GAS
FENCE	— x — x —	— x — x —
GUIDERAIL		
BUSHLINE/TREELINE	~~~~~	~~~~~
CONTOUR	179.00	179.00
SPOT ELEVATION	× 179.00	×179.00
GRADING DIRECTION/GRADE PERCENTAGE	<u>1.9%</u> ⊳	1.9%
DRAINAGE FLOW		~
TRAFFIC SIGN	□ SIGN	▶ SIGN
TRAFFIC POLE/TRAFFIC SIGNAL	O TLS	● P1
LIGHT STANDARD	O LS	• LS
HYDRO POLE	O HP	• HP
GUY WIRE)—	~ '''
BELL POLE	○ <i>BP</i>	•
BELL MAINTENANCE HOLE	O BELL MH	
BELL PEDESTAL/VAULT		
	B	
CABLE PEDESTAL/VAULT	C	
HYDRO TRANSFORMER/VAULT	H	
GAS VALVE	GAS VALVE	
GAS MARKER	⊕ ^{GAS}	
MAILBOX	M	
STANDARD IRON BAR	· SIB	
IRON BAR	■ /B	
TEMPORARY BENCHMARK	↑ TBM#1	
BOREHOLE/TEST HOLE	⊕ BH9	

DISCLAIMER AND COPYRIGHT

CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.

TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.

BENCHMARKS TBM 1 — ELEVATION 265.41 NAIL ON THE SOUTH WEST SIDE OF THE GROSS ROAD AND ASPDIN ROAD INTERSECTION.

TBM 2 — ELEVATION 264.24 NAIL ON THE SOUTH EAST SIDE OF THE 8000 CULVERT WEST OF THE ROSSEAU RIVER CULVERTS.

NOTES		REVISION DESCRIPTION	DATE
 SURVEY COMPLETED BY TATHAM ENGINEERING LTD, APRIL 2025. 		ISSUED FOR REVIEW	JUL 3/25
	2.	ISSUED FOR TENDER	JUL 9/25

ENGINEER STAMP


GROSS ROAD CULVERT REPLACEMENT TOWNSHIP OF MUSKOKA LAKES T-2025-38




IN.01

INDEX

FILE: 225020 DESIGN: AC DATE: MAY 2025 DRAWN: AC CHECK: MS SCALE: AS SHOWN





ENGINEER WITHOUT THE EXPRESS CONSENT OF

Orawing Name: 225020 — GA01.dwg, Plotted: Jul 10, 2025

TATHAM ENGINEERING LIMITED.

- 2. SPECIFICATIONS: OPSS VOLUME 7-8 AND SPECIAL PROVISIONS.
- 4. ALL ELEVATIONS IN METRES, ALL DIMENSIONS IN MILLIMETRES UNLESS OTHERWISE
- 6. FEATURES OF CONSTRUCTION NOT FULLY SHOWN ARE OF THE SAME CHARACTER AS
- 7. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS, DETAILS AND ELEVATIONS THAT ARE RELEVANT TO THE WORK SHOWN ON THE DRAWINGS PRIOR TO COMMENCEMENT OF THE WORK. ANY DISCREPANCIES SHALL BE REPORTED TO THE CONTRACT ADMINISTRATOR AND THE PROPOSED ADJUSTMENT OF THE WORK SHALL BE SUBMITTED
- 8. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING AND PROTECTING ALL EXISTING UTILITIES PRIOR TO AND DURING CONSTRUCTION. LOCATION OF EXISTING UTILITIES TO
- 1. STRUCTURAL PLATE CORRUGATED STEEL PIPE SHALL BE PROVIDED BY OWNER DELIVERED TO SITE AND INSTALLED BY CONTRACTOR. CONTRACTOR WILL TAKE OWNERSHIP OF PIPE MATERIAL UPON DELIVERY. CARE AND CONTROL OF PIPE
- 3. BACKFILL TO BE PLACED IN MAXIMUM 200 mm THICK LAYERS SIMULTANEOUSLY ON ALTERNATING SIDES OF CULVERT. THE MAXIMUM DIFFERENCE IN ELEVATION SHALL BE
- 400 mm. ALL BEDDING AND BACKFILL TO BE COMPACTED TO 100% SPMDD UNLESS 4. BACKFILL MATERIAL SHALL NOT BE DUMPED ONTO THE TOP OF THE PIPE. BACKFILL
- SUITABLE FOR COMPACTING. TRUCK END-DUMPING OR DOZER PLACEMENT AGAINST 5. BACKFILL IN AREAS CLOSE TO THE PIPE SHALL BE COMPACTED USING VIBRATING OR
- TAMPING EQUIPMENT RUNNING PARALLEL WITH THE LENGTH OF THE PIPE AT ALL
- GEOTEXTILE, CENTRED ON JOINT (TERRAFIX 270R OR EQUIVALENT). 7. NO HEAVY CONSTRUCTION EQUIPMENT SHALL BE PLACED WITHIN 1.5 m LATERALLY OF THE STRUCTURE(S) UNTIL THE BACKFILL MATERIAL HAS BEEN PLACED AND
- 8. PRIOR TO ALLOWING HEAVY CONSTRUCTION EQUIPMENT OVER THE STRUCTURE, THE DEPTH OF COMPACTED COVER MATERIAL SHALL NOT BE LESS THAN 600 mm.
- 1. C−1, 35 MPa @ 28 DAYS UNLESS NOTED OTHERWISE.
- 2. MAX AGGREGATE SIZE 20 mm UNLESS OTHERWISE APPROVED.
- 3. ALL MIX DESIGNS AND ADMIXTURES TO BE SUBMITTED TO THE CONTRACT ADMINISTRATOR FOR REVIEW PRIOR TO USE.

- REINFORCING STEEL SHALL BE GRADE 400W.
- 2. UNLESS SHOWN OTHERWISE, TENSION LAP SPLICES FOR REINFORCING STEEL BARS
- 3. ALL INSERTS AND THREADING ARE PART OF REINFORCING STEEL.
- 4. BAR HOOKS SHALL HAVE STANDARD HOOK DIMENSIONS USING MINIMUM BEND DIAMETERS. WHILE STIRRUPS AND TIES SHALL HAVE MINIMUM HOOK DIMENSIONS. ALL HOOKS SHALL BE IN ACCORDANCE WITH THE STRUCTURAL STANDARD DRAWING SS112-1, UNLESS INDICATED OTHERWISE.
- 1. ALL STRUCTURAL STEEL SHALL CONFORM TO CSA G40.20/G40.21. CHANNELS, ANGLES AND PLATES SHALL BE 300W. L SERIES SHEET PILES SHALL BE 260W. ALL OTHER STRUCTURAL STEEL TO BE 350W (UNLESS OTHERWISE NOTED).
- 2. SHEET PILES AND STRUCTURAL STEEL FOR BENT PLATE / SHEETING CAP TO BE GALVANIZED. ZINC COATING MASS (TOTAL ON BOTH SIDES) SHALL NOT BE LESS THAN 915 G/M2 WHEN TESTED BY THE TRIPLE SPOT TEST (TST). FIELD TOUCH UP ALL
- 3. BOLTED CONNECTIONS TO BE ASTM A325 HIGH STRENGTH, UNLESS NOTED OTHERWISE. ALL BOLTS SHALL BE TIGHTENED USING TURN-OF-NUT METHOD AS SPECIFIED IN CSA
- 4. NO DRILLING OR CUTTING AFTER FABRICATION UNLESS APPROVED BY THE CONTRACT
- 5. ALL WELDING SHALL BE AS PER CSA W59 BY A QUALIFIED WELDER UNDER CSA W47.1. ALL WELDS TO BE CONTINUOUS UNLESS NOTED OTHERWISE.
- 6. UNLESS OTHERWISE NOTED, THE MINIMUM FILLET WELD SHALL BE AS FOLLOWS:

MATERIAL THICKNESS OF THICKER PART JOINED (mm)	MINIMUM SIZE OF SINGLE PASS FILLET WELD (mm)
TO 12 INCLUSIVE	5
OVER 12 TO 20	6
OVER 20 TO 40	8
OVER 40 TO 60	10
OVER 60 TO 120	12

- 1. CONTRACT ADMINISTRATOR SHALL REVIEW REINFORCING STEEL AND FORMWORK PRIOR
- 2. CONSTRUCTION JOINTS SHALL ONLY BE MADE AT LOCATIONS SHOWN ON THE
- DRAWINGS OR AS APPROVED BY THE CONTRACT ADMINISTRATOR.
- 4. FALSEWORK SHALL NOT BE REMOVED WITHOUT THE CONTRACT ADMINISTRATOR'S
- 5. A DRAFT GEOTECHNICAL REPORT PREPARED BY CAMBIUM INC. DATED JULY 9, 2025 HAS BEEN REVIEWED IN PREPARATION OF THESE DRAWINGS. THE REQUIRED BEARING PRESSURE AT THE UNDERSIDE OF CULVERT ELEVATION IS 100 kPa SLS AND 150 kPa
- ENGINEER IMMEDIATELY FOLLOWING EXCAVATION. ANY DISTRURBED OR POOR SOILS SHALL BE REMOVED FROM THE EXCAVATED AREA AND REPLACED WITH CONCRETE OR ENGINEERED FILL AT THE DISCRETION OF THE GEOTECHNICAL ENGINEER.
- 7. CULVERT BEDDING SHALL BE PLACED IMMEDIATELY AFTER THE EXCAVATION AND SOILS ARE INSPECTED AND APPROVED BY THE GEOTECHNICAL ENGINEER TO PROTECT THE
- 8. CROSSING OF THE EXISTING STRUCTURE BY CONSTRUCTION EQUIPMENT DURING CONSTRUCTION IS AT THE RISK OF THE CONTRACTOR WHO SHALL TAKE SUCH
- MEASURES AS THEY CONSIDER NECESSARY TO ENSURE SAFE PASSAGE OF EQUIPMENT. 9. EXCAVATIONS SHALL BE PER SOIL CLASS AND OCCUPATIONAL HEALTH AND SAFETY
- 10. ALL IMPORTED FILL MATERIAL TO BE COMPACTED TO MINIMIMUM 98% SPMDD, UNLESS
- 11. ALL PROPRIETARY REPAIR PRODUCTS SHALL BE SELECTED FROM THE MTO DSM (DESIGNATED SOURCES FOR MATERIALS) LIST AND SHALL BE USED IN ACCORDANCE




GENERAL ARRANGEMENT

FILE: 225020 DATE: MAY 2025 SCALE: AS SHOWN CHECK: MS

GA.01


- 1. INSTALL EROSION, SEDIMENT CONTROLS, AND ENVIRONMENTAL PROTECTION MEASURES.
- 2. INSTALL TEMPORARY DIVERSION CHANNEL AND CROSSING
- 3. INSTALL COFFERDAM UPSTREAM AND DOWNSTREAM OF EXISTING CSP BARRELS TO ISOLATE WORKSITE.
- 4. COMPLETE FISH RESCUE.
- 5. COMPLETE SURFACE FEATURE REMOVALS, EXCAVATE, REMOVE EXISTING CSP BARREL, INSTALL NEW CSP BARRELS, INSTALL CUT-OFF WALLS, AND COMPLETE EMBANKMENT REALIGNMENT.
- 6. BACKFILL AND REMOVE COFFERDAM TO DIVERT FLOWS THROUGH NEW BARRELS. 7. COMPLETE REMOVAL OF TEMPORARY DIVERSION CHANNEL AND CROSSING.
- RESTORE ROAD.
- 9. COMPLETE SITE RESTORATION.
- 10. REMOVE EROSION AND SEDIMENT CONTROLS UPON STABILIZATION OF RESTORED AREAS.



TEMPORARY DIVERSION CHANNEL

A CLEAR CHANNEL WIDTH OF 4.0m AT 0.6% SLOPE IS ESTIMATED TO CONVEY THE 2 YEAR DESIGN FLOW AT AN APPROXIMATE DEPTH OF 2.0m. THIS INFORMATION IS PROVIDED AS A COURTESY ONLY. THE CONTRACTOR IS ULTIMATELY RESPONSIBLE FOR THE SECTION OF TEMPORARY WORKS FOR STREAM DIVERSION INCLUDING DIVERSION METHOD, CROSSINGS AND SHORING, AS REQUIRED.

RETURN PERIOD	ESTIMATED WATER SURFACE ELEVATION	ESTIMATED FLOW (m3/s)
2 YEAR	263.2	36.0
10 YEAR	264.1	55.6





PLAN - ENVIRONMENTAL PROTECTION

ENVIRONMENTAL REQUIREMENTS:

- LITRES PER DAY WITHOUT A MINISTRY OF THE ENVIRONMENT, CONSERVATION AND PARKS (MECP) PERMIT TO TAKE WATER OR COMPLETION OF AN ENVIRONMENTAL ACTIVITY AND SECTOR REGISTRY (AS APPLICABLE). 2. THE CONTRACTOR IS RESPONSIBLE FOR PREPARATION, COST AND SUBMISSION OF ALL REPORTS, PLANS AND APPLICATIONS REQUIRED TO SECURE A PERMIT TO TAKE WATER (CATEGORY 1, 2 OR 3) OR ENVIRONMENTAL
- ACTIVITY AND SECTOR REGISTRY (AS APPLICABLE) FROM THE MECP FOR DEWATERING OPERATIONS WHICH EXCEED 50,000 LITRES PER DAY.
- 3. ESTIMATED 2 YEAR FLOW = 36.0 m3/s.
- 4. THE CONTRACTOR IS RESPONSIBLE FOR THE DESIGN OF TEMPORARY WORKSITE ISOLATION, DIVERSION AND DEWATERING SYSTEMS. DIVERSION AND WORK SITE ISOLATION DETAILS IN THE DRAWING SET ARE FOR SCHEMATIC PURPOSES ONLY. THE CONTRACTOR SHALL PROVIDE SUBMISSIONS OF ALL RELEVANT DETAILS FOR THESE WORKS TO THE CONTRACT ADMINISTRATOR FOR REVIEW. ALTERNATIVE SCHEMATICS ARE SUBJECT TO REVIEW BY REGULATORY AGENCIES AND ANY DELAYS FROM SUCH REVIEWS ARE THE RESPONSIBILITY OF THE CONTRACTOR.
- 5. ALL MATERIAL AND EQUIPMENT USED FOR THE PURPOSE OF OR GENERATED DURING COMPLETION OF THE WORKS SHALL BE OPERATED, STORED AND REMOVED FROM SITE IN A MANNER THAT PREVENTS ANY DELETERIOUS SUBSTANCE. (EG. PETROLEUM PRODUCTS, SILT, DEBRIS, ETC.) FROM ENTERING THE WATERCOURSE.
- 6. ANY STOCKPILED MATERIALS SHALL BE STORED AND STABILIZED A MINIMUM OF 30 METRES AWAY FROM AND ABOVE THE HIGH-WATER MARK. STOCKPILES OF ERODABLE MATERIAL SHALL BE SURROUNDED WITH SILT FENCE PER TYPE NOTED ON PLAN OR EQUIVALENT WITHIN 48 HOURS OF STOCKPILING UNLESS THEY ARE TO BE USED/DISPOSED OF WITHIN 14 DAYS.
- 7. IN WATER WORK IS TO OCCUR BETWEEN JULY 15 AND MARCH 14 (INCLUSIVE).
- 8. ALL DISTURBED AREAS SHALL BE STABILIZED AND RE-VEGETATED AS REQUIRED UPON COMPLETION OF WORK AND RESTORED TO A PRE-DISTURBED STATE OR BETTER, INCLUDING RE-INSTATEMENT AND RE-STABILIZATION
- AND MAINTAINED THROUGHOUT CONSTRUCTION, TO PREVENT ENTRY OF SEDIMENT INTO THE WATERCOURSE OR THE MOVEMENT OF RE-SUSPENDED SEDIMENT.
- 10. SEDIMENT AND EROSION CONTROL MEASURES SHALL BE LEFT IN PLACE UNTIL ALL DISTURBED AREAS HAVE BEEN STABILIZED.
- 11. NO WORK IS PERMITTED IN THE WATERCOURSE AND NO MATERIAL SHALL BE RELEASED INTO THE WATERCOURSE. WORK IS TO BE COMPLETED IN THE DRY.
- 12. NO MACHINERY SHALL CROSS THE WATERCOURSE AT ANY TIME. MACHINERY THAT IS REQUIRED ON THE OPPOSITE SIDE OF THE WATERCOURSE WHILE THE STRUCTURE IS BEING REPLACED SHALL BE DRIVEN ACROSS THE STRUCTURE ITSELF, HAULED BY FLOAT, OR DRIVEN AROUND ON ROADS.
- 13. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING ANY TEMPORARY PROTECTION MEASURES OR DEBRIS CONTAINMENT SYSTEMS NECESSARY TO PREVENT ANY CONCRETE, RUBBLE, DEMOLITION DEBRIS, OR DUST FROM ENTERING THE WATERCOURSE. SUCH MATERIAL SHALL BE REMOVED FROM TEMPORARY PROTECTION MEASURES
- REGULARLY AND AT THE END OF EACH DAY. 14. THE SEDIMENT AND EROSION CONTROL MEASURES MAY BE SUBJECT TO CHANGE OR MODIFICATIONS AS A RESULT OF SITE DEVELOPMENT OR CHANGES ON-SITE. REVIEW AGENCIES ARE TO BE NOTIFIED ON ANY SUCH
- 15. ADDITIONAL MATERIALS INCLUDING, BUT NOT LIMITED TO, PUMPS, GEOTEXTILE, SILT FENCE AND CLEAR STONE SHALL BE KEPT ON-SITE FOR REPAIRS TO PROPOSED SEDIMENT AND EROSION CONTROL FEATURES.

- 1. ANY DEWATERING OPERATIONS REQUIRED TO COMPLETE THE WORK IN THE DRY ARE NOT TO EXCEED 50,000 16. EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE EVALUATED ON A WEEKLY BASIS AS WELL AS BEFORE AND AFTER ANY FORECAST PRECIPITATION EVENT. ANY REPAIRS REQUIRED ARE TO BE RECTIFIED
 - 17. SEDIMENT LADEN WATERS ARE TO BE TREATED PRIOR TO DISCHARGING INTO THE WATERCOURSE. 18. MACHINERY, VEHICLES, EQUIPMENT, AND PUMPS SHALL NOT BE REFUELED OR CLEANED WITHIN 30 METRES OF THE WATERCOURSE.
 - 19. ALL MACHINERY SHALL BE MAINTAINED FREE OF FLUID LEAKS AND SHALL ARRIVE ON-SITE IN A CLEAN AND WASHED CONDITION.
 - 20. AN EMERGENCY SPILL KIT SHALL BE KEPT ON SITE AT ALL TIMES. THE CONTRACTOR SHALL COMPLY WITH ALL MECP REQUIREMENTS AND SHALL REPORT SPILLS TO THE SPILLS ACTION CENTRE (1-800-268-6060). A SPILL RESPONSE PLAN IS TO BE KEPT ON SITE AT ALL TIMES.
 - 21. MEASURES SHALL BE TAKEN TO PREVENT CONCRETE LEACHATE FROM ENTERING THE WATERCOURSE. ALL CEMENTITIOUS PRODUCTS INCLUDING CONCRETE, GROUT, AND MORTAR SHALL BE COMPLETELY ISOLATED FROM PRECIPITATION AND WATERCOURSE FLOW FOR A MINIMUM OF 48 HOURS (OR UNTIL SIGNIFICANTLY CURED) TO ALLOW THE PH TO REACH NEUTRAL LEVELS. CONTAINMENT FACILITIES SHALL BE PROVIDED AT THE SITE FOR WASH DOWN OF CONCRETE TRUCKS, PUMPS, EQUIPMENT, AND TOOLS AS REQUIRED.
 - 22. SMALL MESH SEINE TO BE USED TO EXCLUDE FISH FROM THE PROJECT AREA. ALL FISH STRANDED WITHIN THE PROJECT AREA DURING CONSTRUCTION SHALL BE RELOCATED BY A QUALIFIED BIOLOGIST.
 - 23. THE CONTRACTOR SHALL MONITOR THE WEEKLY WEATHER FORECAST ON A DAILY BASIS AND PREPARE THE SITE ADEQUATELY FOR CONDITIONS THAT MAY CAUSE WATER LEVELS TO RISE.
 - 24. ALL GRADES WITHIN THE REGULATORY FLOOD PLAIN ARE TO BE MAINTAINED OR MATCHED UNLESS OTHERWISE
 - 25. ENGINEERED CHANGES TO ESC MEASURES MAY BE NEEDED AS SITE CONDITIONS CHANGE THROUGHOUT THE CONSTRUCTION PROCESS AND MUST REFLECT BEST MANAGEMENT PRACTICES TO CONTROL SEDIMENT AND EROSION ON SITE. UPDATES SHALL BE COMPLETED BASED ON DIRECTION FROM THE CONTRACT ADMINISTRATOR THROUGHOUT THE CONSTRUCTION PROCESS.
- 9. SEDIMENT AND EROSION CONTROL MEASURES SHALL BE IMPLEMENTED PRIOR TO COMMENCEMENT OF WORK, 26. ALL DISTURBED AREAS LEFT INACTIVE FOR 30 DAYS ARE TO BE STABILIZED WITH AN APPROPRIATE SEED MIXTURE PER OPSS.MUNI 804 APPLIED AT A MINIMUM RATE OF 25kg/ha.





DISCLAIMER AND COPY	'RIGH
---------------------	-------

CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.

TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF

BENCHMARKS TBM 1 - ELEVATION 265.41 NAIL ON THE SOUTH WEST SIDE OF THE GROSS ROAD AND ASPDIN ROAD INTERSECTION. TBM 2 - ELEVATION 264.24

WEST OF THE ROSSEAU RIVER CULVERTS.

NAIL ON THE SOUTH EAST SIDE OF THE 8000 CULVERT

NOTES

	No.	REVISION DESCRIPTION	DATE
RVEY COMPLETED BY TATHAM ENGINEERING LTD, RIL 2025.	1.	ISSUED FOR REVIEW	JUL 3/25
	2.	ISSUED FOR TENDER	JUL 9/25

GROSS ROAD CULVERT ENGINEER STAMP T-2025-38

REPLACEMENT **TOWNSHIP OF MUSKOKA LAKES**

ENVIRONMENTAL PROTECTION

17	Т	TA			ΤН			Α		M	
	E	N	G	1	N	E	E	R	I	N	G

DESIGN: AC FILE: 225020 DRAWN: AC DATE: MAY 2025 SCALE: CHECK: MS